chilewich.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- 1.6.1 Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1.6.1.a Floor Tile: Furnish one box for every [50] < Insert number > boxes or fraction thereof, of each type, color, and pattern of floor tile installed.

1.7 QUALITY ASSURANCE

- 1.7.1 Installer Qualifications: A qualified installer who employs workers for this Project who are competent in techniques required by manufacturer for floor tile installation method indicated.
 - 1.7.1.a Engage an installer who employs workers for this Project who are member of the Floor Covering Installation Contractors Association (FCICA) and/or certified by the Certified Floorcovering Installers Association (CFI).
 - 1.7.1.b Engage an installer with minimum of 3 years of experience in installation of flooring products similar in scope and complexity with a minimum of 5 completed projects within the project market within the last 2 years, and participates in manufacturer's environmental program including responsible flooring removal, recycling, and installation.
- 1.7.2 Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
 - 1.7.2.a Build mockups for floor tile including resilient base and accessories. Size: Minimum 100 sq. ft. (9.3 sq. m) for each type, color, and pattern [in locations indicated] [in locations directed by Architect]
 Insert locations in locations indicated.
 - 1.7.2.b Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 - 1.7.2.c Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.8 DELIVERY, STORAGE, AND HANDLING

- 1.8.1 Deliver all materials to the installation site in the manufacturer's original packaging and in good condition. Packaging to contain manufacturer's name and marks, identification number, shipping and handling instructions and related information.
- 1.8.2 Store floor tile and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 68o F (20o C) or more than 75o F (24o C), and measures between 10% and 65% in relative humidity (RH).
- 1.8.3 Environmental Limitations: Do not deliver or install flooring until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature and relative humidity at levels planned for building occupants during the remainder of the construction period.

1.9 FIELD CONDITIONS

1.9.1 Maintain ambient temperatures within range recommended by manufacturer, but not less than [68o F (20o C] or more than [75o F (24o C], in spaces to receive floor tile during the following time periods: